



Bid# 17T212

January 8th, 2018

City of Pembroke Pines
601 City Center Way
Pembroke Pines, FL 33025

Attention: Michael Lockett, *Director of Technology Service*

Project: *East segment fiber phase 2*

Dear Mr. Lockett,

Hypower Inc. is pleased to submit a lump sum pricing proposal for the following sections:

Fire Station #33 – Lump Sum \$126,571.85

Scope of work:

- Design, Permit and Construction.
- Directional Bore (1) 2" Future path conduit approx. 7,317'
- Furnish 8,000' of 2" Future path conduit and Couplings
- Furnish and Install (8) 30x48x36 pull boxes
- Furnish and Install (8,300') of 288ct SMF Micro Fiber optic cable
- Furnish and Install (15) Fiber Marker posts
- Splice up to 24ct at the existing enclosures and terminate up to 24ct at the patch panel. Remaining fibers will be dark.
- OTDR Testing using a launch reel and testing the bare fibers on the end of the lateral to assure the splice is good at each location.

Hypower, Inc.

888-978-9300

954-978-8666

5913 NW 31st Avenue,
Fort Lauderdale, FL 33309

www.hypowerinc.com



Johnson Street Water to Pines Place and to Old Public Services Site – Lump Sum \$442,913.15

Scope of work:

- Design, Permit and Construction.
- Directional Bore (1) 2" Future path conduit approx. 25,615'
- Furnish 26,900' of 2" Future path conduit and Couplings
- Furnish and Install (24) 30x48x36 pull boxes
- Furnish and Install (28700') of 288ct SMF Micro Fiber optic cable
- Furnish and Install (50) Fiber Marker posts
- Splice up to 24ct at the existing enclosures and terminate up to 24ct at the patch panel. Remaining fibers will be dark.
- OTDR Testing using a launch reel and testing the bare fibers on the end of the lateral to assure the splice is good at each location.

Exclusions:

Anything not covered on our scope of work.
This proposal is good for through Mar 2018.

If you should have any questions regarding this proposal, please do not hesitate to contact me.

Sincerely,

Richard Carrero
Division Manager
Communications Division