

QUOTATION

650071672

AMPS

AQUIFER MAINTENANCE & PERFORMANCE SYSTEMS, INC.

7146 Haverhill Road N. • West Palm Beach, FL 33407 • 561-494-2844

February 9, 2017

Pembroke Pines
Pembroke Pines, FL 33444
Attn: Julie Fisher

Re: Wells #9, 11 & 5

AMPS, Inc. appreciates the opportunity to submit the following proposal for your review:

1) 1 – Case epoxy	\$ 425.00
2) 1 – 10"x4" Steel pipe	195.00
3) 1 – 4" 90 degree threaded elbow	105.00
4) 1 – 4" Coupling	59.10
5) Mobilize/demobilize equipment to site	800.00
6) Unbolt & pick up wellhead, seal inside of base plate & well casing with Epoxy, reset wellhead, bolt up & seal with epoxy. Core concrete pad to get to well casing to install 4" vent, fabricate 4" vent onto well casing, form & patch concrete	2,160.00

TOTAL PER WELL: \$ 3,744.10

TOTAL FOR 3 WELLS: \$11,232.30

If you have any questions or comments about the above information please feel free to give us a call. Thank you.

Sincerely,
Jayne L. Prindible
Comptroller

**FOR YOUR TOTAL PUMP & WELL FIELD NEEDS
ABOVE QUOTATION GOOD FOR 30 DAYS.**